


Alternator Test Report

Result PASS

Alternator Type: AL70021
Max amp test: Test date: 07/09/2008 14:07

Test Parameters			Results		
Rotor Rpm	Volts	Amps	Rotor Rpm	Volts	Amps
3000	13.5	Cap in	1538	13.9	16.8
3000	13.5		2071	13.8	34.0
3500	13.5		3008	13.8	48.9
4000	13.5		4059	13.8	54.1
4500	13.5		5004	13.8	57.4
5000	13.5		6025	13.8	60.5
6000	13.5		7106	13.8	62.1
7000	13.5		8051	13.8	62.4
8000	13.5		9265	13.8	62.7

Hot test 95c
Lampless = FALSE



Drawn	NAME	DATE	Drawn
Checked	T.M.	18 08 08	Checked
3RD APPR			
100% APPR			
UNLESS OTHERWISE SPECIFIED:		UNIT: DIMS IN	SCALE: 1:1
DIMENSIONS ARE IN MILLIMETERS		ASSEMBLY	ISSUE: B
CADD FILE		ND A021 100 55	
© Copyright BRIVE LUX Ltd 03 Northport Industrial Estate DA11 90W All Rights Reserved			